

VINOBA BHAVE UNIVERSITY , HAZARIBAG

SHORT RE-TENDER NOTICE

Sealed tenders are invited for the following works at University campus:-

Sl. No.	Name of the work	Estimated Cost
1	Aluminum Partitions in UCET Building & Internal Electrification of UCET Building Partitions in VBU Campus Hazaribag	Rs. 20,77,022.09

Sale of tender papers:- 08-02-2019 to 16 -02-2019 during working hours at Office of Director, UCET on working days only.

Last date of Submission of tender in the office of Director, UCET, VBU, Hazaribag 18-02-2019 by 3 P.M.

For details please visit our website- <http://www.vbu.ac.in> & <http://www.ucetvuhzb.in>

By order of the Vice-Chancellor
Sd/-
Registrar

Memo no:- VBU/UCET/1834/2019

Dated:- 07/02/19

Copy to:

1. The Advertising Manager:
 - (a) Prabhat Khabar, Ranchi
 - (b) Hindustan, Ranchi
 - (c) Dainik Bhaskar, Ranchi
 - (d) Desh Pran

With a request to publish in one edition of your esteemed paper in minimum space and cost and send the bill in triplicate for payment.

2. University & UCET website with a request to float the short tender notice.


Registrar

Vinoba Bhave University, Hazaribag

AK
07/02/2019

7/2/19

07/02/19

Vinoba Bhawe University, Hazaribag

Notice Inviting Tender

(Short Re-Tender Notice)

Tender Reference No. VBU/UCET/1834/2019

Dated:.....

- (1) Sealed tenders are invited in single envelope containing technical bid and price bid from eligible and approved Contractors, registered with Building Construction Department, Govt. of Jharkhand for the works detailed below:

Sl. No.	Name of the work	Estimated Cost	Earnest money	Cost of Tender Paper	Class of Contractor eligibility	Time of Completion
1	Aluminum Partitions in UCET Building & Internal Electrification of UCET Building Partitions in VBU Campus Hazaribag	Rs.20,77,022.09	Rs. 1,05,500.00	Rs. 2,000	III	01 month

Procurement Officer	Place of Opening	Last Date & time of submission of tender	Date & Time of opening of tender
Director, UCET, VBU	Office of Director, UCET, Vinoba Bhawe University, Hazaribag	18-02-2019 upto 3:00 p.m.	To be communicated later on.

- (2) Date of sale of B.O.Q.- 08-02-2019 to 16-02-2019 during working hours at Office of Director, UCET on working days only.
- (3) Cost of tender/bidding document in the shape of demand draft issued by any Nationalized Bank in favour of Director, UCET, Vinoba University, Hazaribag, payable at Hazaribag and cost of earnest money in the shape of Bank guarantee in prescribed Performa as per annexure-1 from any Scheduled public Sector Bank and valid for 180 (one hundred eighty) days from the date of receipt of tender or 6 ½ Years National Saving Certificate (8th issue) or 3/5 Years Post Office Time Deposit duly pledged from any Post Office within the State of Jharkhand, in favour of Director, UCET, Vinoba University, Hazaribag shall be deposited in the office of Director, UCET, Vinoba University, Hazaribag, payable at Hazaribag on all working days between 08-02-2019 to 16-02-2019 up to 05.00 P.M. either by registered post/Speed post or by hand. Only those applications will be entertained whose cost of tender paper and earnest money is received before 05.00 P.M. on 16-02-2019. The university will not be responsible for the postal delay, if any, in the delivery of the document or non-receipt of the same.

Insurance Guarantee Bond/Cash/Cheque/Bank Draft in place of those specified for EMD shall not be accepted.

AK Singh
07/02/2019

Devy
07/02/19

07-02-19

5/12/19

- (4) The Earnest Money of the successful tenderer (hereinafter called the contractor) which accompany the tender will be forfeited in case the tenderer declines to sign the agreement or fails to deposit Security Money within 10 days of being called upon to do so.
- (5) Payment against works will be made subject to availability of fund after statutory deductions as per Government rules.
- (6) Amount of BOQ may increase or decrease.

**Instructions to Bidders
(FOR F₂ CONTRACT)**

Detailed instructions & documents to be furnished for Submitting bidding. :-

1. Guidelines for submission of bids can be downloaded from the website <http://www.vbu.ac.in> & <http://www.ucetvbuhzb.in>
2. Bids will be opened as per time schedule mentioned in the NIT.
3. Bidders should be ready with the self attested Xerox copies of cost of documents & EMD as specified in the tender document. Before submission of bids, bidders must ensure that self-attested Xerox copies of all necessary documents have been attached with bid.
4. Bidders have to produce the original Demand Draft towards tender fee & EMD as mentioned in N.I.T to the Procurement Officer during the period & time as mentioned in the NIT failing which bid will not be accepted.
5. Submitted documents of the successful bidder will be verified with the original before signing the agreement. The successful bidder has to provide the originals to the concerned authority.
6. The university will not be responsible for any delay in submission due to any reason what so ever.
7. All required information for bid must be filled and submitted.
8. Tenderer or his authorized representative (one) may be present at the time of opening of tender.
9. The price bids of those firms will only be opened who are found to be technically qualified after evaluation. The university reserves the right to cancel/reject any or all bids without assigning any reason thereof.

***Self attested xerox copies of following documents are to be submitted.:-**

(a) Technical Bid:-

- i. Name of Tenderer and address with contact number and email-id.
- ii. Name of Work and Estimated Cost.
- iii. D.D. towards Tender fee in favour of Director, UCET, Vinoba University, Hazaribag, payable at Hazaribag.
- iv. Duly pledged EMD in favour of Director, UCET, Vinoba University, Hazaribag, payable at Hazaribag.
- v. Upto date GST return certificate and GST No.
- vi. PAN Card.
- vii. Letter of Registration.
- viii. Income Tax clearance certificate / IT returns of last three years.

AR Singh
07/02/19

AR Singh
07/02/19

AR Singh
07.02.19

AR Singh
07/2/19

- ix. Character Certificate issued by competent authority.
- x. Work Experience of last three years.
- xi. Audited Balance Sheet of last three years.
- xii. Affidavit stating bidder's agreement with the general rules, conditions of contract, special conditions of contract to be submitted with bid. The bidder who disagrees on the conditions will not be eligible to participate in the tender.

(b) Price Bid / Financial Bid.

The bid proposals are to be sealed in two separate envelopes (i) Technical bid (ii) Price bid / Financial bid and kept in one sealed envelope duly addressed as follows:

Tender for the Work	
<p>From,</p> <p>M/s.....</p> <p>Address.....</p> <p>Contact no.....</p> <p>Email-id.....</p>	<p>To,</p> <p style="text-align: center;">The Registrar,</p> <p style="text-align: center;">Vinoba Bhave University,</p> <p style="text-align: center;">Hazaribag- 825301</p>

[Handwritten Signature]
07.02.19

Registrar
Vinoba Bhave University, Hazaribag

AK Singh
07/02/2019

Dileep
07/02/19

V. S. S.
21/2/19

Percentage B.O.Q.


Tender Inviting Authority:- Registrar, Vinoba Bhave University, Hazaribag

Name of the Work:- Aluminium Partitions in UCET Building & Internal Electrification of UCET Building Partitions in VBU Campus Hazaribag

Bidder Name

Price Schedule


Sl. No.	Item No.	Item of Work	Quantity	unit	Rate	Amount
1	5.2.3	Providing designation 75A brick work in C.M. (1:6) in foundation and plinth approved quality of clean coarse sand of F.M. 2 to 2.5 including providing 10mm thick mortar joints, cost of screening materials, raking out joints to 15mm depth, curing, taxes and royalty all complete as per building specification and direction of E/I.				
			7.785	Each	3840.03	29894.81
2	5.3.7.1	providing R.C.C. M-200 with nominal mix of (1:1.5:3) in band at lintel level with approved quality of stone chips 20mm to 6mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position vibrating, skirting, curing, (but excluding the cost of reinforcement, taxes and royalty all complete job as per building specification and direction of E/I.				
			0.354	cu.m	6393.51	2,262.44
3	5.5.4,	Providing Toe steel reinforcement of 8mm dia to 32mm dia rods as approved design and drawing excluding carriage of M.S. bars to work site, cutting, bending and binding with annealed wire with cost of wire, removal of rust, placing the rods in position all complete as per building specification and direction of E/I. TMT Fe 500 (Only Valid for SAIL & TATA Steel)				
		8 mm dia (TMT coil Fe 500) (Only Valid for SAIL & TATA Steel)				
			0.032	Mt	65841.84	2096.93
	5.7.3	Providing 12mm thick cement plaster (1:6) with clean coarse sand of F.M. 1.5 including screening, curing with all leads and lifts of water, scaffolding taxes and royalty all complete as per specification and direction of E/I.				



Handwritten signatures and dates at the bottom of the page, including '24/11/19' and '24/11/19'.

			66.914	sq.m	124.60	8,337.55
5	5.8.18	Providing two coat of oil bound distemper of approved shade and make over a primer coat of cement primer over new surface including preparing the plastered surface by rubbing smooth with pumice stone or fine sand paper applying putty wherever required scaffolding, washing floors and taxes all complete as per building specification and direction of E/I.				
			66.914	sq.m	78.11	5,226.69
6	D.S.R 13.26	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.				
			66.914	sq.m	114.13	7,637.26
7	DSR 21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
7.i	21.1.1.2	For fixed portion - Powder coated aluminium (minimum thickness of powdercoating 50 micron)				
		Take Jindal Section No. 20035 &20036				
		(82.50x38.0x1.60)mm & (82.50x38.0x1.70)mm respectively				
			2022.439	Kg	369.71	7,47,719.04

AK Singh



Director
UCET, VBU, Hazaribag
4-1-19

8	21.1.2.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) - Powder coated aluminium (minimum thickness of powdercoating 50 micron)				
		Take Jindal Section No. 19550 & 19549 SECTION (85x44.45x1.56)mm &(85x44.45x1.62)mm respectively				
			220.610	Kg	427.79	94,374.31
9	DSR 21.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):				
9.i	21.3.2	With float glass panes of 5.50 mm thickness				
		FOR GLAZING 90% AREA	169.210	m ²	965.34	1,63,344.63
10	DSR 21.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge.				
10.i	21.2.2	Pre-laminated particle board with decorative lamination on both sides				
		Take 90% AREA	693.360	Mtr.	833.27	5,77,755.28
11		Carriage of materials Bricks Lead = 1 k+7 P(8km)	3161.27	Thou.	760.62	2,404.52
12		Sand lead = 8 km	3.870	cum	268.27	1,038.12
13		Stone chips lead = 22 km	0.304	cum	518.12	157.68
14	1.3.3	Wiring for light point/fan point/exhaust fan point/ call bell point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable in surface recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size PVC/G.I. boc etc. as required. Group C	80	P/Point	752.00	60160.00
15	1.7	Wiring for Circuit/submain wiring along with earth wire with the following sizes PVC insulated copper conductor, single core cable in surface/recessed PVC conduit as required.				


Handwritten signature

Official stamp: Hazaribagh, Dhanbad, Jharkhand

Handwritten signatures and dates

15.i	1.7.1	2 x 1.5 sq.mm. + 1 x 1.5 sq.mm. earth wire	50	Mtr.	146.00	7300.00
15.ii	1.7.2	2 x 2.5 sq.mm. + 1 x 2.5 sq.mm. earth wire	80	Mtr.	173.00	13840.00
15.iii	1.7.3	2x4.0 Sq.mm + 1x4.0 Sq.mm earth wire.(to be used as sub main for common area like stair case & corridor)	20	Mtr.	211.00	4,220.00
16	1.24	Supplying and fixing following modular type switch / socket on the existing modular plate and switch box including connections but excluding modular plate etc as required.				
16.i	1.24.1	5/6 amps,one way switch	60	Each	59.00	3540.00
16.ii	1.24.3	15/16 amps,one way switch	15	Each	86.00	1290.00
16.iii	1.24.4	5/6 amps, 3 pin socket outlet	10	Each	75.00	750.00
16.iv	1.24.5	15/16 amps, 6 pin socket outlet	15	Each	121.00	1815.00
17	1.31	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 A modular socket outlet and 5/6 A modular switch, connections etc. as required.	15	Each	241.00	3615.00
18	1.32	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 A & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required	15	Each	307.00	4605.00
19	1.34	S/F Batten holder - Supplying and fixing batten/angle holder including connection etc. as required.	15	Each	60.00	900.00
20	1.48	Installation of exhaust fan up to 510mm sweeo in the existing opening, including making the hole to suit the size of the above fan, making good the damage, connection, testing, commissioning etc. as required.	5	Each	472.00	2360.00
21	2.8	Supplying and fixing following way single pole neutral, sheet, MCB disrtibution board, 240 volts, on surface/recess, complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, interconnections, phospatized and powder painted including earthing etc. as required (But without MCB/RCCB/Isolator)				
21.i	2.8.3	6way, single door	8	Each	669.00	5352.00

AK Singh



Director
UCET, VBU, Hazaribag 4/1/19

22	BSR-5.9.1	Supply and Fixing following powder coated batten for 28Watt T5 flourescent tube complete with electronic ballast and lamp etc. directly on wall/ceiling including connecion with 1.5 sq.mm FR PVC insulated copper conductor and earthing the body etc as required. Single	20	Each	957.00	19,140.00
23	JSR Supply 2104	Supply of 12"(300mm) metal exhaust fan	5	Each	1,139.39	5,696.95
24	JSR Supply 2106	Supply of Wall Mounted fan 16" (400 mm)	20	Each	1,904.02	38,080.46
25	Supply 1224	Supply of 20 mm dia ISI marked PVC conduit	4	100 mtr	1,713.80	6,855.20
26	Supply 1225	Supply of 25 mm dia ISI marked PVC conduit	1	100 mtr	2,335.30	2,335.30
27	Supply 1276.	Supply of 72mm x 146mm x 48mm	1	100 nos	3,448.50	3,448.50
28	Supply 1225	Supply of 20 mm M.S clamp	1	100 nos	271.70	271.70
29	Supply 1226	Supply of 20 mm M.S clamp	0.5	100 nos	339.63	169.81
30	Supply 1902	Supply for aluminun armoured cable 10 sq mm, 2 core	50	Mtr.	77.84	3892.00
31	Supply 2231	Supply of 9/10 watt LED bulb	30	Each	141.22	4,236.60
32		Goods & Services Tax (G.S.T.) - 12%	1836122.780		12%	2,20,334.73
33		Labour Cess - 1%	2056457.510		1%	20,564.58
Total in Figures						20,77,022.09
Quoted Rate in Figures	Excess(+)					
	Less (-)					
	Same as estimated rate					
Quoted Rate in Words						

AK Singh



Director
UCET, VBU, Hazaribag

4.11.19